


- 1- (پایه) Support
- صفحات انتهایی -2
- Step (مسدود كننده گوشه ها) -3
- 4- (سطح شيبدار انتهايي) Ramp
- Tile outlet (نوعي از كاشي مورد نياز براي ورودي و خروجي كابل ها) -5
- outlet tile(نوعي از كاشي براي ورود و خروج كابل) -6
- 7. Junction box
- O Junction box 6
- 9_ Junction box data
- 10- نصب میشود) Floor box lid

قطعات مورد نياز براي سولوفلكس:



- support یا پایه هاي هر کاشي
- انواع صفحات مسدود كننده براي بستن كار (در شكل نشان داده شده)
- rampیا سطح شیبدار برای انتهای کار (در شکل نشان داده شده)
 - انواع باكس كف
 - بست هاي ورودي خروجي كابل ها
- و ماژول هاي داخل باكس براي قرار دادن انواع مكانيزم هاي مورد نياز از جمله شبكه ،تلفن ، راديو و

Verp.	Ref.nr.	Floor parts	Verp.	Ref.nr.	Floor parts (continued)
1	84000 10	Tile Pregalvanised Square 225 mm H = 13 mm Provided with 4 contact/distance cams	1	84000 40	Surface-mounted tile (6) Pregalvanised For colonnettes, pedestals + cable worm (see chapter power poles) and lead outlet (ref.no. 81902 32)
1	84120 00	Support ① Black, polypropylene Square 100 mm With 2 square grooves in which tiles can be positioned	1	84000 50	Square 225 mm H = 13 mm Provided with 4 contact/distance projections Fixing bracket Pregalvanised For mounting colonnette (see chapter
1	84000 60	Project edge finishing Pregalvanised L = 900 mm, B = 300 mm 2x turned edge of 13 mm Saw to size on-site for connections			on power poles) onto the constructional floor with surface-mounted tile ref.no. 84000 40 Outlet unitss
1	84000 61	on the wall Edge finishing Pregalvanised L = 900 mm, B = 300 mm 1x turned edge of 13 mm Saw to size on-site for connections	1	81905 09	Junction box 6 V 7 Plastic (black) 1 input GST 18, 1 output GST 18 Pre-wired with 6 branchings GST 18
1	84120 20	on the wall Plenum sealing ② Pregalvanised For sealing the floor in the free space H = 120 mm, L = 900 mm, B = 56 mm	1		Junction box 6 V (a) Pregalvanised 1 input YMVK, 1 output YMVK or lead Pre-wired with 6 branchings Fast Connector and provided with connection terminal with strain relief
1	84120 30	Plenum exterior angle ③ Pregalvanised 56 x 56 mm	1	84000 70 84000 71	Empty Junction box data 8 V Recess for RJ 45 connector
1	84120 40	Ramp 4 Pregalvanised Ramp 10% L = 1181 mm, B = 112 mm Include 1 extra support ref.no. 84120 00 per tray	1	84090 51	Built-in tile square Pregalvanised Square 450 mm For lid & frame assembly square ref.no. 84532 02 or 84538 52 Including wooden disposable cover
1	84000 20	Earthing tile Pregalvanised, square 225 mm H = 13 mm Earthing clamp 6 mm² (max.) 1 tile per 100 m² or in gangways max. 14 metres apart, provided with 4 contact/distance projections	1	84532 02	Plastic lid assembly square (1) Plastic with carpet edge Combine with ref.no. 84090 51 and 84060 74 and/or 84060 69, 84060 80 Lower box data
1	84000 30	Cable outlet tile (5) Pregalvanised Square 225 mm H = 13 mm Recess 125 x 15 mm For lead-through to the workplace	1	84060 74	Pregalvanised 4 double building in data Dependent on R5 connector to be used with data support frame Lower box 230 V
1	81902 32	Provided with 4 contact/distance projections Lead outlet Chromed Apply with surface-mounted tile ref.no. 84000 40 For lead-through to the workplace	1	84060 69 84060 77	Pregalvanised For 4x single Mosaic WCDs Available empty and pre-wired Empty WCD Earthed Mosaic

Soluflex® Cable Floor System H = 120 mm (continued)



Soluflex® Cable Floor System mounting drawings

H = 120 mm






84000 10	84120 00

	04000 10	04120 00
Verp.	Ref.nr.	Outlet unitss (continued)
		Support frame for keystone connectoren
		Plastic To be used in combination with: - substructure universal ref.no. 84060 50 - lower box data ref.no. 84060 74
1	81905 00	Red
1	81905 01	Transparent
1	81905 02	Black
1	81905 03	Yellow
1	81905 04	Green
1	81905 06	Orange
1	81905 08	Brown see overview page 28
		Built-in tile square
1	84090 51	Pregalvanised Square 450 mm For lid & frame assembly square ref.no. 84532 02 or 84538 52 Including wooden disposable cover
1	84538 52	Lid & frame assembly square Plastic with carpet edge Combine with guard large and mounting plate M45 fourfold
1	84090 61	Built-in tile rectangular Pregalvanised Rectangular For built-in cover rectangular ref.no. 84538 51
1	84538 51	Lid & frame assembly rectangular Plastic with carpet edge Combine with guard small and mounting plate M45 threefold
		Built-in tile round
1	84090 71	Pregalvanised Square 450 mm For lid & frame assembly round ref.no. 84548 53
		Lid & frame assembly round
1	84548 53	Aluminium with carpet edge Combine with guard large and mounting plate M45 fourfold
		Mounting box small
1	84550 01	Plastic For lid & frame assembly rectangular
		Mounting plate M45 small
1	84550 31	
1	84550 02	Mounting box large Plastic For round and square lid & frame assemblies
1	84550 32	Mounting plate M45 large Plastic
		For 9 modules Mosaic
1	84550 06	Strain relief Plastic


■ Mounting drawing 1

Mounting of colonnette using surface-mounted tile and fixing bracket




■ Mounting drawing 2

Positioning of the junction box




■ Mounting drawing 3 Mounting of lid & frame assembly in combination with built-in tile




■ Mounting drawing 4

Mounting of lid & frame assembly in combination with built-in tile



■ Mounting drawing 5

Mounting of lid & frame assembly in combination with built-in tile



ساير قطعات (connection):



Flexible Office Design Elements

CASPER YOUR POWERPAL*

Anthracite R7016 synthetic ABS.



	kg/pc
85 945 02	1,6
85 940 12	1,8
85 940 32	1,8
85 940 128	1,8
85 940 129	1,8
85 945 12	1,8
	85 940 12 85 940 32 85 940 128 85 940 129

Specifications:

230 V: Complemented with GST 18 connection cable L=450 mm. Can be connected to a divider block (5x GST)

DATA: Provided with CAT 5E FTP Patch cable L=10 M with RJ45 plug

Empty: Complemented with universal mounting cradle data for specific connectors

Other colours available.

CASPER CABLEDUMP

W = 345, H = 210, D = 107 mm. Used for cable channelling in combination with Casper or other equipment.



Color	Steel	Weight kg/pc
R9006	85 949 05	1,9
R9005	85 949 02	1,9

GST 18 COMPUTER CABLE

3x 1,52.

L = 1,5 mtr.



Synthetic	Weight kg/pc
81 902 21	0,20

CONNECTION CABLE

3 x 1,5 mm², GST 18/3

L = 1,5 mtr.



Synthetic	Weight kg/St.
81 905 17	0,2



FLEXIBEL OFFICE DESIGN ELEMENTS

GST 18 DIVIDER BLOCK (5 x GST)

1x inlet and 5x outlet divider block.



Synthetic	Weight kg/pc
81 902 30	0,05

CABLE DISTRIBUTION BOX CDB-1

Anodised aluminium. Desk connection UNIT 230V / Data. Pre-wired with black outlets 50 x 50 mm. Mounted under the desk.



outlet	Aluminium	Weight kg/pc
\odot	81 905 11	1,0
\odot	81 904 82	1,0
\odot	81 905 118	1,0
	81 905 119	1,0

Specifications:

230V: 1x 2V Normal, 1x 2V UPS DATA: Cat 5 FTP with RJ45 plug 2 x Measurements: 385 x 60 x 50 mm Cable length 5 mtr Specific compilations on request

To use in combination with the Cable Outlet Tile (84 000 30).

CABLE DISTRIBUTION BOX CDB-2

Anodised aluminium. Desk connection UNIT 230V / Data. Pre-wired with black outlets 50 x 50 mm Mounted on the desk.



outlet	Aluminium	Weight kg/pc
\odot	81 905 12	1,25
\odot	81 904 83	1,25
\odot	81 905 128	1,25
	81 905 129	1,25

Specifications:

230V: 2x 230V Normal, 2x 230V UPS DATA: Cat 5 FTP with RJ45 plug 2 x Measurements: 385 x 70 x 70 mm Cable length 5 mtr

Specific compilations on request

To use in combination with the Cable Outlet Tile (84 000 30)

CABLE COMFORT* WITH SERVICEBOX CC/SB-2

Anodised aluminium. Desk connection UNIT 230V / Data. Pre-wired with aluminium coloured outlets Mounted under the desk.



outlet	Aluminium	Weight kg/pc
0	81 905 13	1,8
0	81 904 84	1,8
0	81 905 138	1,8
	81 905 139	1,8

Specifications:

230V: 2x 230V Normal, 2x 230V UPS DATA: Cat 5 FTP with RJ45 plug 2 x Measurements: 450 x 90 x 59 mm Cable length 5 MTR Specific compilations on request

To use in combination with the Cable Outlet Tile (84 000 30)



FLEXIBEL OFFICE DESIGN ELEMENTS

CABLE WORM CW-3

For cable channeling from the floor to the desk connection unit. Grey metallic, 1 closed compartment. Complemented with mounting bracket and base To use in combination with the accessory support tile (8400040)



I	Length in mm	Synthetic	Weight kg/pc
ı	770	81 902 19	0,75

CABLE WORM CW-4

connection unit. Black or grey, open core, 2 compartments. Complemented with mounting bracket and base. L = 760 mm.

For cable channeling from the floor to the desk To use in combination with the accessory support tile (84 000 40)



Colour	Gelakt 9010	Weight kg/pc
black	81 906 41	0,75
grey	81 906 40	0,75

MULTI-OUTLET POWER POST CL1

With 6 double mounting boxes Click it* for universal installation (12 x) and 1 junction box. Cover and base anthracite grey. On request specific pre-wired.

To use in combination with the accessory support tile 8400040 and fixing bracket 8400050 (page 14).



Length	Gelakt	Weight
in mm	9010	kg/pc
670	85 555 03	5,4

MULTI-OUTLET POWER POST CL1

With mounting box Click it* for universal installation and 1 junction box. Cover and base anthracite grey. On request specific pre-wired.

To use as pedestal in combination with the accessory support tile 84 000 40 and fixing bracket 84 000 50 (page 14).



Length in mm	Gelakt 9010	Weight kg/pc
270	85 555 23	3,3
190	85 555 33	2,88



INSTALLATION MATERIALS

DATAFRAME

Synthetic.

To use in combination with:

- Fully submerged unit data 84 060 50 (page 24)
- Built-in unit data 84 060 75 (page. 26, 34).



Data housing to use in combination with floorbox Soluflex 90mm page 35.

Dataframe

Data housing 45 x 45 incl. frame

Туре	Colour	Synthetic	Weight kg/pc
600MJ1	red	81 905 00	<0,1
600MU2	transp.	81 905 01	<0,1
600MU3	black	81 905 02	<0,1
600MJ4	yellow	81 905 03	<0,1
600MU5	green	81 905 04	<0,1
600MU7	orange	81 905 06	<0,1
600MU9	brown	81 905 08	<0.1

Туре	Colour	Synthetic	Weight kg/pc
	red	81 906 31	<0,1
	transp.	81 906 32	<0,1
	black	81 906 33	<0,1
	yellow	81 906 34	<0,1
	green	81 906 35	<0,1
	orange	81 906 37	<0,1
	brown	81 906 39	<0,1

PILL RELIEF

Synthetic.



Synthetic	Weight kg/pc
84 550 06	<0.1

BLIND PLATE

Synthetic.





	Synthetic	Weight kg/pc
1/2	81 904 99	<0,1
1	81 904 97	<0,1

